

If Someone is Planning To Dig On Your Property, Or You Are Doing The Excavation . . . Please Do Your Part!

Look For:

- Pad Mounted Electric Transformers
- Utility Service Wires (Cables attached to the side of the utility pole and entering the ground.)
- Telephone Or Cable Television Pedestals
- Water Valves Or Hydrants
- Regulator Stations, Gas Meters, Valves or Test Stations
- Warning Signs Or Markers
- Manhole Rings and Covers

When you call, please have the following information available:

- Municipality – county, city or township
- Location – street address
- Nearest intersection of streets and roads
- Extent of work ■ Type of work
- Start date and time excavation is scheduled to begin
- Caller's name
- Excavator/contact person and phone number

Even When All Precaution Are Taken, Accidents Can Still Happen. If An Underground Facility Is Hit Or Even Scratched, Please Notify The Facility Operator.

**Dig  Safely.
New York**

- Call Before You Dig
- Wait The Required Time
- Confirm Utility Response
- Respect The Marks
- Dig With Care

800-962-7962
www.digsafelynewyork.com

**Dig  Safely.
New York**


800-962-7962
www.digsafelynewyork.com



What You Should Know Before Getting In Too Deep



TOWN OF DOVER



BUILDING & ZONING DEPARTMENT

126 East Duncan Hill Road
Dover Plains, NY 12522

(845) 832-6689
(845) 832-0370 fax

In addition to Dig Safely New York regulations you must also comply with all Town of Dover Erosion and Sediment Control Regulations (Chapter 65 in the Town Code) and with New York State Erosion and Stormwater Control Laws and Regulations.

Failure to comply with these regulations and laws will result in the immediate revocation of any permits issued or a stop work order issued or the possibility of fines and jail time, or any combination of these measures.

All erosion control measures **MUST** be in place before any excavation is undertaken. In addition, any soil that is to be stripped and stockpiled for a period of longer than 7 days must be seeded down in a manner to prevent erosion. All erosion measurers must be maintained thru the entire construction period and to the extent required after that until the area is stabilized.

Anti-tracking pads must be installed and maintained, dust control measures must be utilized when and where required and portable sanitary facilities will be supplied at all construction site and be maintained as warranted.